

Glendale School District

# Additional Access Doors to the High School

June 14, 2021

Proposal No: 14266

Prepared By:

Jeff Holland

**REECE Complete Security Solutions**

6755 SW Sandburg St, Portland, OR 97223

Tel: 503.682.9900 | Web: [www.rcss.us](http://www.rcss.us)

## SCOPE OF WORK

---

The following proposal is for materials and labor to be provided and installed by REECE Complete Security Solutions

### Access Control System

- (2) Exterior Card Access Control Doors to Include:
  - Card Reader
  - Door Position Switch
  - Request to Exit Device
  - Electrified Strike (to be provided and installed by subcontractor)
  - Includes Access Control Cable to nearest existing access control panel location
- Access Control Panel Equipment to include:
  - (1) S2-MR52-S3 Dual Reader Interface Module
  - (1) Battery Enclosure

Proposal Pricing Based On: Client Request

This proposal contains proprietary and confidential information of REECE Complete Security Solutions and shall not be used, disclosed or reproduced in whole or in part for any other purpose other than to evaluate this proposal without prior written consent of REECE Complete Security Solutions. Title in and to this document and all information contained herein remains at all times with REECE Complete Security Solutions.

PART NUMBER	MFG	DESCRIPTION	QTY	UNIT PRICE	EXT. PRICE
<b>ACS</b>					
<b>CRD-CR-10 - EXT DL</b>					
0E-STLDRMAG	W Box Technologies	3/4 RARE EARTH MAGNET, W Box Technologies, W Box (Wagon Wheel) - Sold in 10 packs	2.00	\$3.59	\$7.18
DOOR CABLE	REECE	Cable from J-Box to Door Devices	1.00	\$66.50	\$66.50
DS160	Bosch	Detector, PIR Request To Exit Sensor w/ Sounder Gray	1.00	\$69.13	\$69.13
910PTNNEK00000	HID	RDR, RP15, MULTICLASS, SE REV E, STD PROX, STD, WIEGAND, PIG, BLK	1.00	\$183.31	\$183.31
6644	GRI	Resistor Pack *Priced Per Each, Must Order In Packs Of 10*	2.00	\$2.75	\$5.50
6132AKC	HID	SPACER ACC KIT, ICLASS R15/RP15, RDR, 0.5", BLK	1.00	\$11.17	\$11.17
N1178CW/ST	Nascom	Switch w/ Leads, 3/4 Inch, Recessed, Extra Wide Gap, Stubby, Commercial, White, For Steel Doors	2.00	\$5.31	\$10.62
LOCK TERMINATION	REECE	Terminate to electrified lock, installed by others or existing. Termination will be made at the fram	1.00	\$33.25	\$33.25
TP160	Bosch	Trim plate for DS150 and DS160	1.00	\$1.48	\$1.48
ACS-S-CMP	Windy City Wire	RCComp2 - 22-3pOAS/22-04/22-04/18-02..	100.00	\$1.09	\$109.00
V-700	Wiremold	700 Series Wiremold	20.00	\$1.69	\$33.89
CONSUMABLES	REECE	As Required but not limited to: EMT, EMT Connectors, Ferrels, Sealtight, Sealtight Connectors, Tape,	1.00	\$133.00	\$133.00
<b>CRD-CR-10 - EXT DL SUBTOTAL:</b>					<b>\$664.03</b>
<b>CRD-CR-11 - EXT DL</b>					
0E-STLDRMAG	W Box Technologies	3/4 RARE EARTH MAGNET, W Box Technologies, W Box (Wagon Wheel) - Sold in 10 packs	2.00	\$3.59	\$7.18
DOOR CABLE	REECE	Cable from J-Box to Door Devices	1.00	\$66.50	\$66.50
DS160	Bosch	Detector, PIR Request To Exit Sensor w/ Sounder Gray	1.00	\$69.13	\$69.13
910PTNNEK00000	HID	RDR, RP15, MULTICLASS, SE REV E, STD PROX, STD, WIEGAND, PIG, BLK	1.00	\$183.31	\$183.31
6644	GRI	Resistor Pack *Priced Per Each, Must Order In Packs Of 10*	2.00	\$2.75	\$5.50
6132AKC	HID	SPACER ACC KIT, ICLASS R15/RP15, RDR, 0.5", BLK	1.00	\$11.17	\$11.17
N1178CW/ST	Nascom	Switch w/ Leads, 3/4 Inch, Recessed, Extra Wide Gap, Stubby, Commercial, White, For Steel Doors	2.00	\$5.31	\$10.62
LOCK TERMINATION	REECE	Terminate to electrified lock, installed by others or existing. Termination will be made at the fram	1.00	\$33.25	\$33.25
TP160	Bosch	Trim plate for DS150 and DS160	1.00	\$1.48	\$1.48
ACS-S-CMP	Windy City Wire	RCComp2 - 22-3pOAS/22-04/22-04/18-02..	150.00	\$1.09	\$163.50
V-700	Wiremold	700 Series Wiremold	20.00	\$1.69	\$33.89
CONSUMABLES	REECE	As Required but not limited to: EMT, EMT Connectors, Ferrels, Sealtight, Sealtight Connectors, Tape,	1.00	\$133.00	\$133.00
<b>CRD-CR-11 - EXT DL SUBTOTAL:</b>					<b>\$718.53</b>
<b>PNL-ACP-3 - EXISTING</b>					
S2-MR-52-S3	Lenel	Mercury MR52 Reader Interface Module	1.00	\$566.58	\$566.58
BC400SG	Altronix	Battery Enclosure	1.00	\$88.96	\$88.96
CONSUMABLES	REECE	As Required but not limited to: EMT, EMT Connectors, Ferrels, Sealtight, Sealtight Connectors, Tape,	1.00	\$133.00	\$133.00
<b>PNL-ACP-3 - EXISTING SUBTOTAL:</b>					<b>\$788.54</b>
<b>ACS SUBTOTAL:</b>					<b>\$2,171.10</b>
<b>Additional Labor</b>					
DEVICE		DEVICE - Labor	28.90	\$105.00	\$3,034.47
CABLE		CABLE - Labor	15.00	\$95.00	\$1,425.00

DESIGN	DESIGN - Labor		5.00	\$110.00	\$550.00
DRAFT/DOC	DRAFT/DOC - Labor		4.00	\$65.00	\$260.00
PROGRAM	PROGRAM - Labor		2.00	\$110.00	\$220.00
PROJMGMT	PROJMGMT - Labor		7.00	\$115.00	\$805.00
TRAVEL	TRAVEL - Labor		8.00	\$70.00	\$560.00

**ACS SUBTOTAL: \$6,854.47**

**OTH**

**OTHER ITEMS**

PERMITS	REECE	Electrical Permit	1.00	\$166.67	\$166.67
SUBCONTRACTOR HARRYS	REECE	Subcontractor	1.00	\$2,367.86	\$2,367.86
PERDIEM	REECE	Perdiem Costs including Hotel, Food, and Other Related Travel Expenses	1.00	\$1,500.00	\$1,500.00
WARRANTY	REECE	Workmanship Warranty	1.00	\$0.00	\$0.00

**OTH SUBTOTAL: \$4,034.53**

## TERMS AND CONDITIONS

### Exclusions & Clarifications

- All 120V Power Required for Devices and Systems in this proposal is to be provided and installed by Others unless otherwise noted.
- All 120V Surge Protection Required for Devices and Systems in this proposal is to be provided and installed by Others unless otherwise noted.
- All Pathways, Conduit, Wiremold, Cable Tray, Back-Boxes, Junction Boxes, etc. Required for Devices and Systems in this proposal by Others unless otherwise noted.
- Network POE and/or PoE+ Switches Required for Devices and Systems in this proposal by Others unless otherwise noted.
- IP Addresses Required for Devices and Systems in this proposal to be provided by others unless otherwise noted.
- Monitors, PC's, Viewing Stations, etc. Required for Devices and Systems in this proposal by Others unless otherwise noted.
- Patching and Painting by Others unless otherwise noted.
- Cable installed by Others must be pulled to device location unless otherwise noted.
- Excludes Lift Rental unless otherwise noted.
- Excludes Backboards unless otherwise noted.
- Excludes Network Cabinets and Racks unless otherwise noted.
- Excludes configuration and troubleshooting of customer's network, including but not limited to, switches, routers, existing copper, fiber, and wireless networks. Configuration and troubleshooting of customer's network by REECE would be performed and invoiced separately on a Time and Materials Change Order upon customer approval.
- VOIP System Programming Required for Devices and Systems in this proposal by Others unless otherwise noted.
- Existing Access Control System unless otherwise noted.
- Existing Video Management System unless otherwise noted.
- Existing Intrusion Detection System unless otherwise noted.
- Includes Permit and Inspection as Required.
- Changes to design and/or scope may result in additional charges.
- All work to be performed during regular business hours.
- One-Year Warranty from substantial completion on workmanship, manufacturer's warranty applies to REECE-supplied material.
- Materials marked "OFE" are Owner Furnished Equipment, installed by REECE, provided by others.
- Terminations to electrified lock hardware that is installed by others or existing will be done as follows:  
Terminations will be made at the frame side of the hinge for electrified panic bars, lever sets and mortise locks.  
Terminations will made directly to electrified strikes, mag locks, overhead door motors and gate openers.
- Proposal pricing assumes that existing equipment is fully functional. Troubleshooting, repair, and replacement of existing equipment will be performed on a Time and Materials change order upon customer approval.
- Proposal pricing assumes that existing cable is fully functional. Troubleshooting, repair, and replacement of existing cable will be performed on a Time and Materials change order upon customer approval.
- Idle time incurred due to absence of required escorts, clearances, inability to enter the workspace, or other factors beyond our control will be considered a change in the contract and may result in additional charges.
- Price valid 30 Days from Date of Proposal. Payment is due Net 30 Days from invoice.

## QUOTE SUMMARY

<b>BILL TO:</b>	<b>SHIP TO:</b>
Glendale School District 100 Pacific Ave. Glendale, OR 97442	Glendale High School 10598 Azalea Glen Road Glendale, OR 97442

## PROJECT EQUIPMENT AND LABOR

Description	Amount
Purchased Equipment:	\$3,837.77
Installation Services:	\$9,222.33
Freight Total:	\$65.13
Misc. Total	\$96.65
<b>Total One Time Charges</b>	<b>\$13,221.88</b>

## MAINTENANCE AGREEMENT

Description	Amount
<b>Service Support Agreement</b>	<b>\$0.00</b>

All applicable sales taxes extra.

*This Quote shall become binding on the parties hereto when signed by Subscriber and accepted and approved by REECE Complete Security Solutions. By Customer's signature, Customer acknowledges that they have read, understood and agreed to REECE Complete Security Solutions Terms and Conditions.*

## CLIENT APPROVAL

Submitted By: REECE Complete Security Solutions

Accepted By: Glendale School District

09/27/2021

Date

Date

Jeff Holland

Print Name

Print Name



Signature

Signature